

DEMOLITION NOTES THIS SHEET

- 1 REMOVE DUCTWORK, GRILLES AND DIFFUSERS, INSULATION, HANGERS AND SUPPORTS COMPLETE TO POINT INDICATED. PROVIDE TEMPORARY AIRTIGHT CAPS WHERE DUCT WILL BE RECONNECTED.
- 2 REMOVE HIGH PRESSURE VARIABLE AIR VOLUME BOX AND ASSOCIATED PNEUMATIC THERMOSTAT AND TUBING. SEE NEW WORK ON DRAWING M1.2G. TEMPORARILY CAP CONTROL AIR SOURCE.
- 3 REMOVE CEILING MOUNTED UNIT HEATER, HANGERS AND SUPPORTS.
- 4 REMOVE CEILING MOUNTED FAN CONTROL UNIT OR UNIT VENTILATOR, HANGERS, AND SUPPORTS. REMOVE ALL ASSOCIATED DUCTWORK, THERMOSTAT AND CONTROL WIRING.
- 5 REMOVE FLOOR MOUNTED UNIT VENTILATOR, REMOVE EXTERIOR WALL LOUVER. PROVIDE INSULATED SHEET METAL CAP. COORDINATE WITH ARCHITECT.
- 6 REMOVE ROOF HOOD. PROVIDE INSULATED SHEET METAL CAP OVER ROOF CURB. CROSS BREAK TO PREVENT OIL PANNING.
- 7 REMOVE ROOFTOP EXHAUST FAN AND DUCTWORK COMPLETE. PROVIDE INSULATED SHEET METAL CAP OVER ROOF CURB. CROSS BREAK TO PREVENT OIL PANNING.

ASBESTOS AND LEAD PAINT NOTE

AN ASBESTOS INSPECTION WAS PERFORMED AND ASBESTOS CONTAINING MATERIALS WERE FOUND GENERALLY IN THE AREAS INDICATED IN THE ASBESTOS SURVEY/INSPECTION REPORT WHICH IS AVAILABLE TO THE CONTRACTOR(S) FOR HIS INFORMATION. ASBESTOS CONTAINING MATERIALS HAVE BEEN REMOVED UNDER A SEPARATE CONTRACT.

A LEAD-BASED PAINT INSPECTION WAS PERFORMED AND LEAD-BASED PAINT WAS FOUND IN THE AREAS INDICATED. THE CONTRACTOR SHALL BE RESPONSIBLE WITH ALL REQUIREMENTS OF THE VIRGINIA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS LEAD-BASED PAINT PROTECTION OF WORKERS.



GRAPHIC SCALES

3/16" = 1'-0" 0' 5' 10' 20'

nbij ARCHITECTURE
A Professional Limited Company
GROVE PARK SQUARE
11537-B NUCKOLS ROAD
Richmond, Virginia 23069
☎ (804) 273-9611 fax: (804) 273-9843




**RAPPAHANNOCK
COMMUNITY COLLEGE**
CAMPUS RENOVATIONS
WARSAW + GLENN'S, VIRGINIA
PC: 260-17712

**GLENN'S CAMPUS
DEMOLITION FLOOR**
PLAN – MECHANICAL DUCTWORK

Date: JANUARY 13, 2010

REVISIONS	
NO.	DATE



Sheet
MD1.5G
File Number
XX